<u>Kind Attn: - FOR REFERECNE, COMPANY REGISTERED ADDRESS, CITY NAME, GST NO: (IF AVAIL) (Dated on 29- 04-2020)</u>

Sub: Offer for Sanitization Disinfected Tunnel

Dear Sir,

Thanks for inquiry, Refer to our discussion we are pleased to submit herewith our most suitable offer for Human Sanitization disinfected tunnel.

This offer describes the structure and design of above equipments. This document is intended for the specification and identification of the equipment.

We hope our offer is in line with your requirement. Looking forward for your acceptance of our offer. In case you require further clarification in this regard. Please revert to us.

Thanking you,

Yours

faithfully, For Aashna Engineers,

Chitrang Patel

Mobile no.: +91 9913475579 email:aashnaengineers@yahoo.com

TECHNICAL SPECIFICATION

Sanitization Disinfected Booth / Tunnel

STRUCTURE	The structure will be in 30 mm x 30 mm MS Square Pipe and for horizontal and vertical support 30 mm x 30mm MS Rectangular Pipe (Or As per requirement)	
PANELLING	Vinyl Flex / FRP Sheet/ACP-Aluminum composite panel/polycarbonate solid sheet	
Vinyl Flex / FRP Sheet/ACP-Aluminum Composite panel/ polycarbonate solid sheet		

BOTTOM FLOORING	NA		
DOOR	NA- Only open space for Entry and Exit		
Entrance/Exit	PVC Curtain Strips		
PAINTING	All components of MS structure are painted internally as well as externally with one coat primer and two coats of color.		
PVC Spray Nozzle	4 nos for 4x4x8 ft And other sizes also avail		
Person capacity at a time	1 at a time for 4x4x8 ft		
Power supply	230 V AC , 50 HZ ,300 Watt		
ELECTRIC FITTING	Included		
Control Method	Manual , AUTO Optional		
PLUMBING	PVC Pipe provision with nozzles inside the tunnel to provide proper misting		
Man Detection Sensor	Available in Auto operation only		
Storage tank	100 Litter Storage tank		
Pump	Provided		
LCD Touch Display	Optional - Inbuilt in Automatic		
Relay card	Optional - Inbuilt in Automatic		
Liquid level detection Sensor	Optional - Inbuilt in Automatic		
DISINFECTANT SYSTEM	The humidifier converts the disinfectant into fine mist and releases it inside the tunnel thus by reducing the chances of cross-contamination as significant amount of pathogens will be		
	made ineffective from the surface; once you pass through the tunnel		



PRODUCT EQUIPMENTS IMAGES FOR REFERENCE ONLY











Aashna Engineers

Customer Trust is Our Value...









Please Note:


The Humidifier should be off for 15 minutes after every 2 to 3 hours for long life

We provide 100 liter double layer tank along with the system so full day solution can be poured and be ready in tank which can be merged with the It is advisable to use prepared solution to use in 36 hours of time.

We provide disinfectant tunnel, portable disinfection gateway, portable sanitizing booth, portable full body sanitizing machine, sanitizing chamber, spray sanitizing tunnel etc. in manual and automated operating mode.

*(Image is for reference only – it may look differ as per selection of material (there is polycarbonate solid sheet in image)







THERE IS AUTOMATIC PROCESS, THERE IS NO HUMAN OR ANY SURFACE CONTACT WITH PERSON




THERE IS NONE REQUIRE FOR THIS PROCESS, WE NEED TO ADD DISINFACTANT IN CYCLE



NO MANUAL PROCESS TO REDUCE INFECTION THREATS old X





WHY TO USE:

- IT CAN BE USED WITH WORKING CLOTHS
- BY PASSING THROUGH MIST SPRAYED TUNNEL, THE RISK OF INFECTION CAN BE REDUCED
- PROVIDE SAFETTY FROM COVID-19 AND OTHER VIRUS AND MICRO ORGANISMPRESENT ON HUMAN BODYOR CLOTHS
- ENGANCES THE HYGIENCE OF PEOPLE, VISITING STAFF

_

Quotation For sanitizing Booth on Polycarbonate sheet/FLEX,FRP/3-4MM ACP/1.2MM TO 2MM METAL SHEET ETC. on steel structure

Sr.No	Item	Quantity	Rate/Each
1	Sanitization Booth 4 x 4x 8	01	22000/- RS. TO
	Ft(wxdxh)(Manual)		28500/- RS.
2	Sanitization Booth 4 x 4x 8	01	40000/- RS. TO
	Automatic control- touch display ,panel		48000/- RS.
	and controller(AUTOMATIC SYSTEM)		



Terms and Condition.

- 1. Above Price is Ex. Ahmedabad.
- 2. Packaging and forwarding, Transportation charges will be extra at actual.
- 3. GST will be extra at actual.
- 4. Payment Terms: 40% along with Purchase Order. Balance against Performa invoice at delivery.
- 5. Delivery will be 2 to 4 Weeks from the date of purchase order.
- 6. Disinfection Solution will be provided by client...If required it will be charge extra.
- 7. These Rates are fir Minimum 10 Nos Quantity.
- 8. Insurance will be covered by client.
- 9. Any dispute subject to Ahmedabad (India) jurisdictional only
- 10. Unloading and shifting will be arranged by clien

We hope our offer in line with your requirement and now looking forward to receive your valued order. In case of any queries please revert back to us.

Yours faithfully, For,

AASHNA ENGINEERS,

Chitrang Patel

Authorized Signatory